Notice dated 22nd December 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 15th January 1929, for constructing Hay-platforms at Mysore Lancers, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3. (*a*) Percentages less or above sanctioned estimate will not be accepted.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Hay-platforms at Mysore Lancers" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for constructing Hay-platform at Mysore Lancers.

No.	Items of work	Quantity	Per unit	Rate
1	Earthwork excavation, gravelly soil	16	C.yds.	
2	Concrete in chunam	168	C.ft.	
3	Burnt stone slabs 4″ to 6″ thick with rough dressing and fixing.	668	S.ft.	
4	Flooring with asphalt 2″ thick on 3 to 4″ concrete bed ...	48·00	Sqr.	
5	Iron steel girders 3″×6″	56¼	Cwt.	
6	Angle iron with fixing 14,658 lbs. or	120·88	„	
7	Zinc sheet roofing including bolts, nuts, washers, etc. ...	103·40	Sqr.	
8	Drain in centre with zinc sheet...	120	R.ft.	

H. R. VENKATASUBBA RAO,
Executive Engineer.

KOLAR DIVISION.

Notice dated 26th December 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M of 29th January 1929 for restoring Rampur-Ramasayi Tank Registered No. 40 of Goribidnur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees 300 (three hundered only) in cash or Goveonment Promissory Notes, as earnest money, and be supercribed "Tender for restoring Rampur-Ramasayi Tank Registered No. 40 of Goribidnur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate for restoring Rampur-Ramasayi Tank Registered No. 40 of Goribidnur Taluk.

No.	Details of work	No.	Quantity	Rate	Cost
	I. Bund.				
1	Eathwork with watering and tamping, etc., complete.	C.yds.	4,790		
2	Turfing	S.yds.	4,968		
3	Removing and resetting old stone work ..	C.yds.	906		
4	New stone work	,,	837		
5	B. M. stones	No	2		
6	Grade with index stones	,,	23		
7	Gauge stone	,,	1		
8	Registered No. and date stone ..	,,	1		
9	Cutting trenches and removing prickly pears and ant hills, etc.	Gade	15		
	Total ...	...	...	...	...
	II. Constructing sluice at R. L. 45·00.				
1	Dismantling the existing sluice after cut opening the bund and refilling the same at C. S. No. 8.	L. S.	...		
2	Earthwork	C.yds.	60		
3	Surki concrete	C.ft.	295		
4	Burnt brick in surki mortar ...	,,	164		
5	Stone slabs 6″ thick	S.ft	195		
6	Plastering with surki mortar ..	Sqrs.	4·55		
7	Cutting holes in slabs ...	No	3		
8	Providing plug and rod with lock and key system.	L. S.	..		
	Total for sluice ...	...	...	..	...
	III. Constructing a weir at R. L. 50·00 *to a length of* 85′.				
1	Earthwork	C.yds.	311		
2	Surki concrete	C.ft.	248		
3	Burnt brick in surki mortar ..	,,	274		
4	Burnt stone slabs 6″ thick... ..	Sq.ft.	146		
5	Plastering	Sqrs.	4·50		
6	New stone work	C.yds.	39		
	Total weir ...	..	..	...	..

N. LAKSHMINARASIMHAIYA,
Executive Engineer.